Pembroke Foundry cross-dock receipt memo

Emberline School District is the administrative client context for the March build. Customer-owned castings move during the night-shift trailer turn window directly from the inbound trailer to the outbound load. Material is not put away or racked.

For each receipt line, compare the quantity against the receiving paperwork and record both the expected quantity and the received quantity. Check packaging condition, label and traceability legibility, and visible damage.

A shortage, visible damage, illegible traceability, or failed inspection is recorded in the exception note. Such a finding is held or escalated according to the supplied handoff contact while the outbound truck is present. The record identifies the receipt date, load, line, item, reviewer, and review time.